

CONVENTIONAL FRAME
ALL OPEN AREAS

INDICATES DIRECTION OF LAYOUT (24" O.C, U.O.N.)



BEARING HEIGHT SCHEDULE

	10' 1-1/8"
	20' 7"
	22' 7"

NOTES:

1.) REFER TO HIB 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING.) REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED.

2.) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V105 FOR ALTERNATE BRACING REQUIREMENTS.

3.) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.

4.) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.

5.) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.

6.) SY42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.

7.) BEAM/HEADER/LINTEL (HDR) TO BE FURNISHED BY BUILDER.

Builders FirstSource

Jacksonville
PHONE: 904-772-6100 FAX: 904-772-1973

Tampa
PHONE: 813-621-9831 FAX: 813-628-8956

Freeport
PHONE: 850-835-4541 FAX: 850-835-6835

BUILDER: Dreambuilder Custom Homes

LEGAL ADDRESS: Lot 5 The Sanctuary

MODEL:		Revision:
2617		Rev. By:
DATE: 04/28/11	DRAWN BY: MCI	Original Reference #: 368531
1st Level Job#:: 371415	2nd Level Job #::	Roof Job#: 368531

MITEK PLATE APPROVAL #'s 2197.2 - 2197.4, WEYERHAUSER PRODUCT #'s 1630.2 - 1630.10