



**BEARING HEIGHT SCHEDULE**

	10' 1-1/8"
	11' 5-1/8"
	20' 9"

- NOTES:**
- 1) REFER TO HD 91 (RECOMMENDATIONS FOR HANDLING INSTALLATION AND TEMPORARY BRACING). REFER TO ENGINEERED DRAWINGS FOR PERMANENT BRACING REQUIRED.
  - 2) ALL TRUSSES (INCLUDING TRUSSES UNDER VALLEY FRAMING) MUST BE COMPLETELY DECKED OR REFER TO DETAIL V109 FOR ALTERNATE BRACING REQUIREMENTS.
  - 3) ALL VALLEYS ARE TO BE CONVENTIONALLY FRAMED BY BUILDER.
  - 4) ALL TRUSSES ARE DESIGNED FOR 2' o.c. MAXIMUM SPACING, UNLESS OTHERWISE NOTED.
  - 5) ALL WALLS SHOWN ON PLACEMENT PLAN ARE CONSIDERED TO BE LOAD BEARING, UNLESS OTHERWISE NOTED.
  - 6) 5Y42 TRUSSES MUST BE INSTALLED WITH THE TOP BEING UP.
  - 7) BEAM/HEADER/LINTEL (HDR) TO BE FURNISHED BY BUILDER.



**Jacksonville**  
 PHONE: 904-772-6100 FAX: 904-772-1973

**Tampa**  
 PHONE: 813-621-9831 FAX: 813-628-8956

**Freeport**  
 PHONE: 850-835-4541 FAX: 850-835-6835

BUILDER: Dreambuilder Custom Homes		
LEGAL ADDRESS: Lot 2 Avalon		
MODEL: Cromer Res.	Revision: 2/6/13	Rev. By: GEB
DATE: 01/17/12	DRAWN BY: GEB	Original Reference #: 460040
1st Level Job #: 462843	2nd Level Job #: 462843	Roof Job #: 460040

MITEK PLATE APPROVAL #'s 2197.2 - 2197.4, WEYERHAUSER PRODUCT #'s 1630.2 - 1630.10